

NEW MEXICO DEPARTMENT OF TRANSPORTATION				CN: D3025		LETTING DATE: 01/19/2007	
Length: 5.230 Miles			Project No. IM-025-4(121)249			Project #1	
Time: 90 Working Days						Bid Bond: 5% Page 1 of 2	
Project Description: 1-25, MP 248.770 to MP 254.000 located in Sandoval County							
LineNo.	AltCode	ItemNumber	Quantity	Unit	LongDesc	UnitPrice	Bid Amounts
Section 0001- Roadway							
10		201000	1	LS	CLEARING AND GRUBBING		
20		203000	9300	C.Y.	UNCLASSIFIED EXCAVATION		
30		207000	25720	S.Y.	SUBGRADE PREPARATION		
40		208000	1.6	MILE	LINEAR GRADING		
50		304000	18240	TON	BASE COURSE		
60		304800	1	LS	BASE COURSE/SUBBASE TESTING BY THE CONTRACTOR		
70		404000	2630	TON	OPEN GRADED FRICTION COURSE		
80		405000	2282	S.Y.	DETOUR PAVEMENT CONSTRUCTION		
90		407000	50	TON	BITUMINOUS MATERIAL FOR TACK COAT		
100		408100	30	TON	PRIME COAT MATERIAL		
110		414002	5010	C.Y.	COLD MILLING (BITUMINOUS) STOCKPILED		
120		422282	27090	TON	PLANT MIX BITUMINOUS PAVEMENT (PMBP) SP-III COMPLETE		
130		422500	1	LS	PMBP SAMPLING & TESTING BY THE CONTRACTOR		
140		515000	4	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES		
150		570024	338	L.F.	24" CULVERT PIPE		
160		570025	2	EACH	24" CULVERT PIPE END SECTION		
170		570030	192	L.F.	30" CULVERT PIPE		
180		570036	32	L.F.	36" CULVERT PIPE		
190		570037	2	EACH	36" CULVERT PIPE END SECTION		
200		601000	1	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS		
210		601110	12320	S.Y.	REMOVAL OF SURFACING		
220		602000	200	C.Y.	RIPRAP CLASS A		
230		602020	80	C.Y.	RIPRAP CLASS C		
240		602060	56	S.Y.	RIPRAP CLASS G		
250		602200	270	C.Y.	GABIONS		
260		603100	8.2	ACRE	TEMPORARY SOIL STABILANT		
270		603221	530	L.F.	CHECK DAM TYPE II		
280		603250	14	EACH	DROP INLET PROTECTION TYPE I		
290		603260	1728	S.Y.	CULVERT PROTECTION		
300		603270	1	ALOW	SWPPP PLAN PREPARATION ALLOWANCE	15000	
310		603280	1	LS	SWPPP MANAGEMENT		
320		606000	337.5	L.F.	METAL BARRIER W-BEAM		
330		606010	37.5	L.F.	METAL BARRIER THRIE BEAM		
340		606050	1	EACH	METAL BARRIER END TREATMENT (ANCHORAGE)		
350		606100	1	EACH	METAL BARRIER END TREATMENT (ANCHORAGE) TYPE A		
360		606600	120	L.F.	TEMPORARY CONCRETE WALL BARRIER		
370		618000	1	LS	TRAFFIC CONTROL MANAGEMENT		

380		621000	1	LS	MOBILIZATION		
390		622001	1	EACH	FIELD LABORATORY, TYPE I		
400		622110	1	EACH	SUPPLEMENTAL FIELD LABORATORY (SUPERPAVE)		
410		622200	1	EACH	FIELD OFFICE		
420		623002	1	EACH	MEDIAN DROP INLET, TYPE I, 2' TO 3'		
430		623003	1	EACH	MEDIAN DROP INLET, TYPE I, 3' TO 6'		
440		623201	1	EACH	MODIFIED MEDIAN DROP INLET, TYPE I		
450		631000	39990	L.F.	RUMBLE STRIPS		
460		632000	6.8	ACRE	CLASS A SEEDING		
470		632410	1329	L.F.	WATTLES		
480		701000	605	S.F.	PANEL SIGNS		
490		701010	580	S.F.	EXTRUDED PANEL SIGNS		
500		701020	1015	S.F.	RETROREFLECTIVE SHEETING FIELD OVERLAY PANELS		
510		701100	1040	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS		
520		701109	77	L.F.	STEEL I-BEAM POST TYPE W6X9		
530		701116	33	L.F.	STEEL I-BEAM POST TYPE W6X16		
540		701118	37	L.F.	STEEL I-BEAM POST TYPE W8X18		
550		701209	4	EACH	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST W6X9		
560		701216	2	EACH	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST W6X16		
570		701218	2	EACH	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST W8X18		
580		702000	1886	S.F.	CONSTRUCTION SIGNING		
590		702100	1608	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING		
600		702110	45	EACH	PORTABLE SIGN SUPPORT		
610		702238	8	EACH	BARRICADE, TYPE III-8'		
620		702310	350	EACH	VERTICAL PANEL, TYPE SINGLE		
630		702525	600	EACH	CHANNELIZATION DEVICES TYPE DRUM		
640		702600	2	EACH	SEQUENTIAL ARROW DISPLAY		
650		702610	4	EACH	PORTABLE CHANGEABLE MESSAGE SIGN		
660		703110	13	EACH	ROAD DELINEATOR TYPE HAZARD		
670		703400	40	EACH	1/10TH MILE DELINEATOR		
680		704000	2260	L.F.	RETROREFLECTORIZED PAINTED MARKINGS		
690		704700	190000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS		
700		704735	6	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW		
710		704862	30	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE TG		
720		704863	30	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE TH		
730		801000	1	LS	CONSTRUCTION STAKING BY THE CONTRACTOR		