

<b>New Mexico Department of Transportation</b>				<b>CN: D4047</b>		<b>Letting Date: 02/16/2007</b>	
<b>Length: 3.600 miles</b>			<b>Project No. IM-025-6(86)411</b>			<b>Project #1</b>	
<b>Time: 45 Working Days</b>						<b>Bid Bond: 5%</b>	
<b>Page 1 of 1</b>							
<b>Project Description: 1-25, MP 411.700 to MP 415.300 located in Colfax County.</b>							
LineNo.	AltCode	ItemNumber	Quantity	Unit	LongDesc	UnitPrice	Bid Amount
<b>Section 0001- Roadway</b>							
10		203200	384	C.Y.	SUBEXCAVATION		
20		404000	3395	TON	OPEN GRADED FRICTION COURSE		
30		407000	37	TON	BITUMINOUS MATERIAL FOR TACK COAT		
40		414000	323000	SYIN	COLD MILLING (BITUMINOUS)		
50		422282	15290	TON	PLANT MIX BITUMINOUS PAVEMENT (PMBP) SP-III COMPLETE		
60		422500	1	LS	PMBP SAMPLING & TESTING BY THE CONTRACTOR		
70		618000	1	LS	TRAFFIC CONTROL MANAGEMENT		
80		621000	1	LS	MOBILIZATION		
90		622002	1	EACH	FIELD LABORATORY, TYPE II		
100		622110	1	EACH	SUPPLEMENTAL FIELD LABORATORY (SUPERPAVE)		
110		702801	1	LS	TRAFFIC CONTROL DURING CONSTRUCTION		
120		704000	85600	L.F.	RETROREFLECTORIZED PAINTED MARKINGS		
130		801000	1	LS	CONSTRUCTION STAKING BY THE CONTRACTOR		