

New Mexico Department of Transportation				CN: 3590		Letting Date: 02/16/2007	
Length: 7.315 miles		Project No. AC-EBS-(TPM)-0256(1)07				Project # 3	
Time: 220 Working Days						Bid Bond: 5% Page 1 of 2	
Project Description: NM 256, MP 0.000 to MP 7.315 located in Chaves County							
LineNo.	AltCode	ItemNumber	Quantity	Unit	LongDesc	UnitPrice	Bid Amount
Section 0001- Roadway							
10		201000	1	LS	CLEARING AND GRUBBING		
20		203000	26600	C.Y.	UNCLASSIFIED EXCAVATION		
30		203100	3500	C.Y.	BORROW		
40		203200	1000	C.Y.	SUBEXCAVATION		
50		207000	93100	S.Y.	SUBGRADE PREPARATION		
60		303000	39100	TON	BASE COURSE		
70		404000	4100	TON	OPEN GRADED FRICTION COURSE		
80		407000	80	TON	BITUMINOUS MATERIAL FOR TACK COAT		
90		408100	145	TON	PRIME COAT MATERIAL		
100		415000	99400	S.Y.	PAVEMENT SURFACE RESTORATION		
110		417000	9140	S.Y.	MISCELLANEOUS PAVING		
120		423282	30700	TON	PLANT MIX BITUMINOUS PAVEMENT (PMBP) SP-III COMPLETE		
130		570024	16	L.F.	24" CULVERT PIPE		
140		570030	120	L.F.	30" CULVERT PIPE		
150		570048	30	L.F.	48" CULVERT PIPE		
160		570055	2	EACH	54" CULVERT PIPE END SECTION		
170		570160	208	L.F.	35"SX24"R (NOMINAL) CULVERT PIPE ARCH		
180		570166	174	L.F.	57"SX38"R (NOMINAL) CULVERT PIPE ARCH		
190		601000	1	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS		
200		603270	1	ALOW	SWPPP PLAN PREPARATION ALLOWANCE	15000	
210		603280	1	LS	SWPPP MANAGEMENT		
220		604003	3000	S.Y.	GEOTEXTILE CLASS 3		
230		604310	3000	S.Y.	GEOGRID BASE REINFORCEMENT		
240		607004	27500	L.F.	BARBED WIRE FENCE 4'		
250		607014	7500	L.F.	WOVEN WIRE FENCE 4'		
260		607316	22	EACH	STANDARD GATE, 16'		
270		607324	2	EACH	STANDARD GATE, 24'		
280		610036	7	EACH	CATTLE GUARD 36'		
290		618000	1	LS	TRAFFIC CONTROL MANAGEMENT		
300		621000	1	LS	MOBILIZATION		
310		631000	56870	L.F.	RUMBLE STRIPS		
320		632000	8	ACRE	CLASS A SEEDING		
330		632410	8994	L.F.	WATTLES		
340		667110	17	EACH	MAIL BOX INSTALLATION-SINGLE		
350		667120	5	EACH	MAIL BOX INSTALLATION-DOUBLE		
360		667130	7	EACH	MAIL BOX INSTALLATION-MULTIPLE		
370		701000	1625	S.F.	PANEL SIGNS		

380	701100	3768	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS		
390	702810	1	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION		
400	703003	8	EACH	OBJECT MARKER TYPE 3		
410	703100	16	EACH	ROAD DELINEATOR TYPE GUIDE		
420	704000	260000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS		
430	704320	2	EACH	RETROREFLECTORIZED PLASTIC RIGHT ARROW		
440	704330	16	EACH	RETROREFLECTORIZED PLASTIC LEFT ARROW		
450	704400	9	EACH	RETROREFLECTORIZED PLASTIC WORD (ONLY)		
460	704610	2	EACH	RETROREFLECTORIZED PLASTIC RAILROAD CROSSING (BIKEWAY)		
470	801000	1	LS	CONSTRUCTION STAKING BY THE CONTRACTOR		
480	901000	1	LS	CONTRACTOR PROCESS QUALITY CONTROL		