

New Mexico Department of Transportation			CN: BR076			Letting Date: 03/16/07	
Length: 1.231 Miles			Project No. EBS-IM-(BR)-040-1(126)21			Project #3	
Time: 140 Working Days						Bid Bond: 5% Page 1 of 2	
Project Description: I-40, MP 20.997 to MP 22.228 located in McKinley County							
LineNo.	AltCode	ItemNumber	Quantity	Unit	LongDesc	UnitPrice	Bid Amount
Section 0001- Roadway							
10		304000	4694	TON	BASE COURSE		
20		304800	1	LS	BASE COURSE/SUBBASE TESTING BY THE CONTRACTOR		
30		404000	196	TON	OPEN GRADED FRICTION COURSE		
40		407000	13.5	TON	BITUMINOUS MATERIAL FOR TACK COAT		
50		408100	24	TON	PRIME COAT MATERIAL		
60		422281	7595	TON	PLANT MIX BITUMINOUS PAVEMENT (PMBP) SP-II COMPLETE		
70		422500	1	LS	PMBP SAMPLING & TESTING BY THE CONTRACTOR		
80		570024	84	L.F.	24" CULVERT PIPE		
90		601000	1	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS		
100		601110	9262	S.Y.	REMOVAL OF SURFACING		
110		604003	9262	S.Y.	GEOTEXTILE CLASS 3		
120		604310	9262	S.Y.	GEOGRID BASE REINFORCEMENT		
130		606000	937.5	L.F.	METAL BARRIER W-BEAM		
140		606010	5912.5	L.F.	METAL BARRIER THRIE BEAM		
150		606050	3	EACH	METAL BARRIER END TREATMENT (ANCHORAGE)		
160		606100	1	EACH	METAL BARRIER END TREATMENT (ANCHORAGE) TYPE A		
170		606619	5600	L.F.	RESETTING OF CONCRETE WALL BARRIER		
180		606620	5600	L.F.	STATE FURNISHED CONCRETE WALL BARRIER		
190		608004	560	S.Y.	CONCRETE SIDEWALK 4"		
200		609450	990	L.F.	CONCRETE BARRIER CURB AND GUTTER TYPE B 8" X 30"		
210		613000	1	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES		
220		618000	1	LS	TRAFFIC CONTROL MANAGEMENT		
230		621000	1	LS	MOBILIZATION		
240		630100	5200	L.F.	MULTIPLE GLARE SHIELDING		
250		631000	4590	L.F.	RUMBLE STRIPS		
260		702000	1304	S.F.	CONSTRUCTION SIGNING		
270		702100	1972	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING		
280		702110	32	EACH	PORTABLE SIGN SUPPORT		
290		702238	20	EACH	BARRICADE, TYPE III-8'		
300		702525	200	EACH	CHANNELIZATION DEVICES TYPE DRUM		
310		702600	2	EACH	SEQUENTIAL ARROW DISPLAY		
320		702610	4	EACH	PORTABLE CHANGEABLE MESSAGE SIGN		
330		704000	88000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS		
340		704100	70000	L.F.	REMOVABLE MARKING TAPE		
350		704862	400	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE TG		
360		704863	400	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE TH		
370		720100	2	EACH	SAND BARREL VEHICULAR IMPACT ATTENUATOR UNIT		

380		720110	2	EACH	REMOVE AND RESET		
390		721000	3000	L.F.	REMOVAL OF PAVEMENT STRIPE		
400		801000	1	LS	CONSTRUCTION STAKING BY THE CONTRACTOR		
Section 0001 Total:							
Section 0002-Bridge							
410		210000	556	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES		
420		511200	72	S.Y.	STRUCTURAL CONCRETE, CLASS A-4"		
430		511300	60	C.Y.	SUBSTRUCTURE CONCRETE CLASS A		
440		511500	11970	S.F.	SPECIAL SURFACE FINISH		
450		512000	636	C.Y.	SUPERSTRUCTURE CONCRETE		
460		514042	744	L.F.	CONCRETE BARRIER RAILINGS 42"		
470		515000	4	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES		
480		529000	1	LS	PIER AND ABUTMENT BEARING MODIFICATIONS		
490		530300	1200	LB	REPLACEMENT REINFORCING BARS GRADE 60		
500		533000	44	S.Y.	REPAIR OF CONCRETE STRUCTURES		
510		534000	20	GAL	EPOXY INJECTION, TYPE I		
520		534010	8	GAL	EPOXY INJECTION, TYPE II		
530		540160	138340	LB	EPOXY COATED REINFORCING BARS GRADE 60		
540		541000	4852	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES		
550		601000	1	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS		